PARTICLE PHYSICS DIVISION OPERATING MANUAL REVIEW AND APPROVAL RECORD

ELECTRICAL WORK PERMITS

Revised by	Name/ID#	Date	11/25/08
Approved by	PPD Head	_ Date	12/1/08

ELECTRICAL WORK PERMITS

INTRODUCTION

Work on AC power distribution systems at Fermilab is controlled by Electrical Work Permits. This includes work performed by employees, T&M subcontractors, and Fixed Price subcontractors. The AC work control document presently in existence is described and included in the Fermilab ES&H Manual, Chapter 5042.

RESPONSIBILITIES

Supervisors, Project Managers and Task Managers shall ensure that the procedures in Chapters 2060, 5041, 5042, 5048 and 5120 of the Fermilab ES&H Manual are followed.

The PPD Electrical Coordinator (designated by the Division Head and listed in the PPD Task Manager List) will approve Electrical Work Permits (EWP's). To ensure adequate and independent review, Electrical Co-ordinator may not approve EWP's for which they are the Task Manager.

The Task Manager shall transmit a copy of each signed work permit to the PPD Head immediately after it has been signed. The originator of the Electrical Work Permit form shall notify the appropriate building manager of the impending work.

The PPD Head will approve all permits involving work on energized electrical systems (see PPD ADMIN 001).

DESCRIPTION

The originator of the Electrical Work Permit shall evaluate the work to be done and provide a description of the work, a list of hazards associated with the specific job, and details of how each hazard will be addressed and mitigated. Specific information with regard to Lock-out/Tag-out requirements shall be included on the EWP. The EWP will also function as the Hazard Analysis where the only hazard is of an electrical nature.

The Task Manager should sign as the Preparer and have the Electrical Work Permit approved by the PPD Electrical Coordinator. Any permits involving work on energized electrical systems must be authorized by the designated PPD Electrical Coordinator AND the Particle Physics Division Head AND the Directorate.

NOTE: Where Lock-out/Tag-out is required, both the person performing the electrical work AND the Task Manager will be required to independently verify that the electrical equipment is de-energized prior to beginning the work.

PPD ES&H Manual PPD ESH 018 Rev.7/31/2009

Exp. 11/23/2011

Revision History

Author(s)	Description	Revision	Date
A. Sands	Add document control disclaimer and revision history page	7/31/09	7/31/09