

XFT Review

XFT

Upgrade

XFT Stereo Finder Finder Hardware Status

(FNAL)


T. Shaw



XFT Stereo Block Diagram

XFT

Upgrade





RX Mezzanine


XFT


Upgrade

Optical data



Electrical data








Stereo XFT RX Mezzanine Test Setup

XFT

Upgrade



Error rate observations:

two 3 day running periods

zero errors observed during one three day period

3 errors observed during another three day period

Bit Error Rate = 3 errors / (20bits/16E-9s)*6days*24hr/day*60min/hr*60s/min)

= 5E-15



Stereo XFT PCB Status

XFT

Upgrade

PCB Manufacture/Assembly Job released to Compunetix, Inc. on December 6, 2004

- 5 boards due back in 6 weeks -> Jan. 21, 2005
- 16 layer Board (8 signal/8 planes) 9Ux400mm format
- All parts are in hand and will be shipped to vendor by the end of the week



Board Testing

XFT

Upgrade

Boards will be individually tested

Initial

JTAG to check connectivity

VME slave responses

FPGA download

Algorithm Tests


load data in FPGAs, pump through and inspect results



XFT Stereo Layout

XFT

Upgrade






Transition Module – Link to

XFT

Upgrade



9U x 400mm Main Module

Transition Module



Transition Module

XFT

Upgrade

Custom design for Transition Module has been schematically captured

- 2 serial optical links provided off the transition module
- each stream will contain identical information
- 8b/10b encoding utilizing TLK1501 serializer
- data stream to be received by the 4 Channel RX_Mezz which is also used on the Stereo XFT main board



Slam Driver Issue

XFT

Upgrade

Current plan calls for using the 4 channel TX_Mezz to drive signals to the SLAM

This presents a problem – the SLAM configuration requires 6 optical channels of data (3 copies each of two independent data streams)

Two possible solutions:

Use a 1:2 passive optical splitter cable

These are ordered and will be tested ASAP

Build a 6 channel mezzanine module



Schedule

XFT

Upgrade

Stereo Finder Schedule (set in June'04)

Finish Schematics early Sept'04

Finish Layouts early Oct'04

Preproduction Board under test early Dec'04

we expect to begin above in late January'05

Testing complete early Mar'05

Production Readiness Review 3/21/05

Production checkout done late July'05